

Schedule of Quantity for the work" Construction of road from Bidulata House to Sarada Tripathy House in ward no-18, NAC, Athagarh"

Sl. No.	Description of the work proposed for exeuction	Qty.	Unit	Rate	Amount
1	Earth work in excavation in all kinds of soil including dressing & levelling the bed & depositing soil within initial lead & lift.	32.16	Cum	300.83	9673.49
2	Supplying and filling the foundation and plinth with clean coarse river sand of approved quality from approved quarry, laying in layers not exceeding 150mm thick, watering and ramming including cost, conveyance royalty and taxes of all materials, cost of as per the direction of Engineer-In-Charge	16.08	Cum	1475.70	23726.30
3	Providing cement concrete(1:3:6) by using 40mm size hard granite metal(cb) including cost, conveyance & roylaty of all materials etc.	16.08	Cum	5941.00	95519.40
4	Providing cement concrete (1:2:4) by using 12mm size hard granite metal (cb) including cost, conveyance & royalty of all materials etc.	16.08	Cum	7580.60	121880.89
6	Removal of excavataed and dismantled materials by machanical means to an average lead of 5km.	32.16	Cum	278.77	8964.13
7	Provision for Transparency Board	1.00	Item	9000.00	9000.00
				Total Estimated cost	268764.21
				Say	268764.00

Rupees Two Lakh Sixty Eight Thousand Seven Hundred Sixty Four Only

Asst. Engineer,
NAC,Athagarh

Municipal Engineer,
NAC, Athagarh

Executive Officer,
NAC, Athagarh

To be filled in by the Contractor participating in the tender process

My quoted reate are

_____ % (_____) Excess

OR

_____ % (_____) Less

Over the estimated cost as put to tender

Signature of Contractor