

Schedule of Quantity for the work"Renovation of Kothaghara near nabagraha temple in w. no.3,NAC, Athgarh"

Sl. No.	Description of the work proposed for exeuction	Qty.	Unit	Rate	Amount
1	Providing 6mm thick cement plaster(1:4) with deep chipping & slurry treatment including cost, conveyance & royalty of all materials etc.	48.83	Sqm	300.83	14689.53
2	Fixing Marble in floors or steps & landing on 25mm. thick bed of CM (1:1) jointed with neat cement slurry including rubbing & polishing including cost , conveyance & royalty of all materials etc.	30.86	Sqm	1598.70	49335.88
3	Providing weather coat two coat over a coat of primer including cost & conveyance of all materials etc.	48.83	Sqm	184.50	9009.14
4	Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32 mm x 32 mm x 2 mm in 3 rows in stair case as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T&P etc. required for the complete in all respect.C/C and stainless square pipe bracing of size case as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T&P etc. required for the complete in	30.0	Mtr	3626.80	108804.00
5	Fixing Digital wall Tiles to dados skirting & risers on 12mm. thick C.P (1:3) jointed with neat cement slurry with cost, conveyance & royalty of all materials etc.	23.70	Sqm	1425.40	33781.98
6	2.5cm. thick grading concrete (1:2:2)on roof slab with 6mm. Size on new work crusher broken hard Granite chips including cost of all labour, materials with all taxes, lead, T & P etc all complete.	33.04	Sqm	398.20	13156.53
7	Fixing Chequered Tiles in floors or steps & landing on 25mm. thick bed of cement mortar (1:1) jointed with neat cement slurry mixed with pigment to match the shades of the tiles all complete with & without cost of precast Chequered tiles.	24.00	Sqm	755.70	18136.80
8	Provision for Transparency Board	1.00	Item	9000.00	9000.00
				Total Estimated cost	255913.85
				Say	255914.00

Rupees Two Lakhs Fifty Five Thousand Nine Hundred Fourteen Only

Asst. Engineer,
NAC, Athgarh

Municipal Engineer,
NAC, Athgarh

Executive Officer ,
NAC, Athgarh

To be filled in by the Contractor participating in the tender process

My quoted reate are

_____ % () Excess

OR

_____ % () Less

Over the estimated cost as put to tender

Signature of Contractor