

**Schedule of Quantity for the work"Repiar & renovation of Harisaranpur Creamatorium W.no-10 NAC,Athagarh."**

Sl. No.	Description of the work proposed for exeuction	Qnty.	Unit	Rate	Amount
1	Earth work in excavation in all kinds of soil including dressing & levelling the bed & depositing soil within initial lead & lift.	8.88	Cum	300.83	2671.37
2	Supplying and filling the foundation and plinth with clean coarse river sand of approved quality from approved quarry, laying in layers not exceeding 150mm thick, watering and ramming including cost, conveyance rovaltv and taxes of all materials. cost of as per the	4.44	Cum	1475.70	6552.11
3	Providing cement concrete(1:3:6) by using 40mm size hard granite metal(cb) including cost, conveyance & roylaty of all materials etc.	4.44	Cum	5941.00	26378.04
4	Fixing Chequred Tiles in floors on 25mm. thick bed of CM (1:1) jointed with cement slurry without cost of precast tiles.	38.09	Sqm	755.7	28780.83
5	Providing cement concrete (1:2:4) by using 12mm size hard granite metal (cb) including cost, conveyance & royalty of all materials etc.	2.08	Sqm	7580.60	15797.97
6	6 mm thick cement plaster (1:4) to R CC surfaces finished smooth including closed deep chiping and slury treatment	3.30	Sqm	185.00	610.87
7	scraping old paint with scrapers,sand papering and washing with soap water or soda including scaffolding charges upto hight 5m	93.33	Sqm	5.12	477.82
8	Providing weather coat two coats over a coat of primer with approved quality and shade over piastered surface with brush including cleaning the surface watering curing ,cost of paint ,taxes,labour charges T & P etc complete as per the direction of engineer in charge.	127.98	Sqm	184.50	23611.39
9	Providing Rigid & smooth centering & shuttering for concrete work	7.92	Sqm	249.80	1978.42
10	Providing Fly ash brick masonry in cement mortar (1:6) in Supper Structure including cost, conveyance & royalty of all materials etc of all materials, labour, T&P etc. and as per direction of Engineer in charge	2.43	Cum	5764.50	14007.74
11	Poviding 16mm thick cement Plaster (1:6) over brick masonry including cost , conveyance & royalty of all materials etc.	20.40	Sqm	288.10	5877.24
12	RCC M-20 by using 12mm to 20mm size crusher broken hard granite chips including cost,conveyance & royalty of all materials.				
	(a) wall Beam	0.41	Cum	18144.00	7348.32
	(b) Roof Slab	1.11	Cum	13700.82	15139.41
13	Straghtning, cutting, bending & binding the MS rod & placing in proper position including cost & conveyance of MS rod & bending wire 18 gauge etc	1.29	Qntl	8712.10	11229.90
14	Provision for Transparency Board	1.00	item	9000.00	9000.00
				<b>Total Estimated cost</b>	<b>169461.42</b>
				<b>Say</b>	<b>169461.00</b>

Rupees One Lakh Sixty Nine Thousand Four Hundred Sixty One Only

Asst. Engineer,  
NAC,Athagarh

Municipal Engineer,  
NAC, Athagarh

Executive Officer,  
NAC, Athagarh

**To be filled in by the Contractor participating in the tender process**

**My quoted reate are**

\_\_\_\_\_ % ( ) Excess

**OR**

\_\_\_\_\_ % ( ) Less

**Over the estimated cost as put to tender**

**Signature of Contractor**

