

Schedule of Quantity for the work"Repiar & renovation of Abhiram Paramhansa Community Centre in W. no.13, Athgarh NAC."

Sl. No.	Description of the work proposed for exeuction	Qnty.	Unit	Rate	Amount
1	Providing Fly ash brick masonry in cement mortar (1:6) in Supper Structure including cost, conveyance & royalty of all materials etc of all materials, labour, T&P etc. and as per direction of Engineer in charge.	9.00	Cum	5764.50	51880.50
2	Poviding 16mm thick cement Plaster (1:6) over brick masonry including cost , conveyance & royalty of all materials etc.	3.34	Sqm	288.10	961.10
3	6 mm thick cement plaster (1:4) to R CC surfaces finished smooth including closed deep chiping and slury treatment	8.54	Sqm	185.00	1579.90
4	Supplying, fitting & fixing MS Window and Window grill including cost & conveyance of all materials etc.	218.55	kg	90.00	19669.50
5	Providing enamel painting two coat over a coat of primer including cost & conveyance of all materials etc.	14.64	Sqm	265.80	3891.11
6	RCC M-20 by using 12mm to 20mm size crusher broken hard granite chips including cost,conveyance & royalty of all materials.				
	(a)Lintel	1.20	Cum	14118.05	16941.66
	(b)Chajja	0.43	Cum	1234.99	526.11
	(c) Roof	4.09	Cum	13700.82	56087.05
	(b) Roof Beam	1.94	Cum	18144.00	35271.94
7	Straghtning, cutting, bending & binding the MS rod & placing in proper position including cost & conveyance of all materials etc.	6.67	Qntl	8712.10	58149.43
8	Provision for Transparency Board	1.00	item	9000.00	9000.00
				Total Estimated cost	253958.30
				Say	254000.00

Rupees Two Lakh Fifty Four Thousand Only

Asst. Engineer,
NAC,Athagarh

Municipal Engineer,
NAC, Athagarh

Executive Officer,
NAC, Athagarh

To be filled in by the Contractor participating in the tender process

My quoted reate are

_____ % () Excess

OR

_____ % () Less

Over the estimated cost as put to tender

Signature of Contractor

