

Schedule of Quantity for the work" Construction of road from Fani Bhaina House to Main Road,ward no -9, NAC, Athagarh"

Sl. No.	Description of the work proposed for exeuction	Qty.	Unit	Rate	Amount
1	Earth work in excavation in all kinds of soil including dressing & levelling the bed & depositing soil within initial lead & lift.	40.19	Cum	300.83	12088.85
2	Supplying and filling the foundation and plinth with clean coarse river sand of approved quality from approved quarry, laying in layers not exceeding 150mm thick, watering and ramming including cost, conveyance royalty and taxes of all materials, cost of as per the direction of Engineer-In-Charge	21.62	Cum	1475.70	31904.63
3	Providing cement concrete(1:3:6) by using 40mm size hard granite metal(cb) includng cost, conveyance & roylaty of all materials etc.	21.62	Cum	5941.00	128444.42
4	Providing cement concrete (1:2:4) by using 12mm size hard granite metal (cb) includng cost, conveyance & royalty of all materials etc.	30.08	Cum	7580.60	228024.45
5	Providing Rigid & smooth centering & shuttering for concrete work	56.40	Sqm	249.80	14088.72
6	Provision for Transparency Board	1.00	Item	9000.00	9000.00
				Total Estimated cost	423551.08
				Say	423551.00

Rupees Four Lakh Twenty Three Thousand Five Hundred Fifty one Only

Asst. Engineer,
NAC,Athagarh

Municipal Engineer,
NAC, Athagarh

Executive Officer,
NAC, Athagarh

To be filled in by the Contractor participating in the tender process

My quoted reate are

_____ % (_____) Excess

OR

_____ % (_____) Less

Over the estimated cost as put to tender

Signature of Contractor