

**Schedule of Quantity for the work" Construction of Road from Kalia Bhai house to Siria Behera house in Ward no-9, NAC, Athagarh. "**

Sl. No.	Description of the work proposed for exeuction	Qty.	Unit	Rate	Amount
1	Dismantling & removing the old cement concrete including stacking the useful materials for reuse & removing the debris within initial lead & lift.	2.70	Cum	862.30	2328.21
2	Providing cement concrete(1:3:6) by using 40mm size hard granite metal(cb) includng cost, conveyance & roylaty of all materials etc.	1.94	Cum	5941.00	11495.84
3	Providing cement concrete (1:2:4) by using 12mm size hard granite metal (cb) includng cost, conveyance & royalty of all materials etc.	52.88	Cum	7580.60	400892.45
4	Provision for Transparency Board	1.00	Item	9000.00	9000.00
				<b>Total Estimated cost</b>	<b>423716.50</b>
				<b>Say</b>	<b>423716.00</b>

**Rupees Four Lakh Twenty Three Thousand Seven Hundred Sixteen Only**

**Asst. Engineer,**  
NAC,Athagarh

**Municipal Engineer,**  
NAC, Athagarh

**Executive Officer,**  
NAC, Athagarh

**To be filled in by the Contractor participating in the tender process**

**My quoted reate are**

\_\_\_\_\_ % ( \_\_\_\_\_ ) Excess

**OR**

\_\_\_\_\_ % ( \_\_\_\_\_ ) Less

**Over the estimated cost as put to tender**

**Signature of Contractor**