

Schedule of Quantity for the work" Construction of road from Durga Behera house to Bikash Behera house in ward no-9, NAC, Athagarh"

Sl. No.	Description of the work proposed for exeuction	Qty.	Unit	Rate	Amount
1	Dismantling & removing the old cement concrete including stacking the useful materials for reuse & removing the debris within initial lead & lift.	5.00	Cum	862.30	4311.50
2	Providing cement concrete(1:3:6) by using 40mm size hard granite metal(cb) includng cost, conveyance & roylaty of all materials etc.	4.20	Cum	5941.00	24952.20
3	Providing cement concrete (1:2:4) by using 12mm size hard granite metal (cb) includng cost, conveyance & royalty of all materials etc.	50.70	Cum	7580.60	384336.42
4	Providing Rigid & smooth centering & shuttering for concrete work	1.00	Sqm	249.80	249.80
5	Provision for Transparency Board	1.00	Item	9000.00	9000.00
				Total Estimated cost	422849.92
				Say	422850.00

Rupees Four Lakh Twenty Two Thousand Eight Hundred Fifty Only

Asst. Engineer,
NAC,Athagarh

Municipal Engineer,
NAC, Athagarh

Executive Officer,
NAC, Athagarh

To be filled in by the Contractor participating in the tender process

My quoted reate are

_____ % (_____) **Excess**

OR

_____ % (_____) **Less**

Over the estimated cost as put to tender

Signature of Contractor