

**Schedule of Quantity for the work" Repair of Hari Saranpur Kothagarh in w. no.10 ,NAC,Athagarh."**

Sl. No.	Description of the work proposed for exeuction	Qnty.	Unit	Rate	Amount
1	Dismantling and removing 2.5 cm thick grading concrete including staking the useful materila for reuse & removing the debris within initial lead & lift.	34.54	Sqm	130.40	4504.02
2	Providing ,fixing of false ceiling with Aluminium anodised T section No. 3215 with 2feet C/C ,L section 1705 up to 15 micron on 4 walls to be fixed by means of steel screw P.V.C plug Alumunium grid to feet into grid suspended from ceiling etc all complete. including cost of scaffolding staggng charges with cost of all materials ,labour, T & P etc all complete	26.46	Sqm	1644.00	43492.02
3	scraping old paint with scrapers,sand papering and washing with soap water or soda including scaffolding charges upto hight 5m	187.70	Sqm	5.12	961.02
4	Supplying, fitting and fixing vetrified tile in floors of size 600mm x 600mm of approved make confirming to IS 13755 laid on 20 mm thick cement mortar 1:4 and filling joints with white cement of approved quality including cost of all materials, labour T&P etc required for the work all complete as per direction of Engineer in charge.( For new work only)	26.46	Sqm	1149.80	30417.96
5	Fixing Wall Tile to dados skirting & risers of steps on 12mm. thick C.P (1:3) jointed with neat cement slurry mixed with pigments to match the shade of wall	34.08	Sqm	978.00	33329.26
6	Distemper two coat with approved quality and shade over one coat of wall primer of approved	17.27	Sqm	174.00	3004.11
7	weather coat two coats with approved quality and shade over one coat of wall primer of approved shade on new work to give an even shade including cost & conveyancy of all material etc	72.27	Sqm	184.50	13333.82
8	Providing enamel painting two coat over a coat of primer including cost & conveyance of all materials etc.	7.95	Sqm	265.80	2113.11
9	4cm. thick grading CC (1:2:4) on roof slab with 12mm. Size hard broken & down grade Size on old work	34.54	Sqm	834.00	28806.36
10	Provision for Transparency Board	1.00	item	9000.00	9000.00
				<b>Total Estimated cost</b>	<b>168961.67</b>
				<b>Say</b>	<b>168962.00</b>

**Rupees One Lakh Sixty Eight Thousand Nine Hundred Sixty Two Only**

**Asst. Engineer,**  
NAC,Athagarh

**Municipal Engineer,**  
NAC, Athagarh

**Executive Officer,**  
NAC, Athagarh

**To be filled in by the Contractor participating in the tender process**

**My quoted reate are**

\_\_\_\_\_ % ( \_\_\_\_\_ ) Excess

**OR**

\_\_\_\_\_ % ( \_\_\_\_\_ ) Less

**Over the estimated cost as put to tender**

**Signature of Contractor**

