

Schedule of Quantity for the work" Repair of Sati Chaura Sahi Kothaghara in ward no-10, NAC, Athagarh"

| Sl. No. | Description of the work proposed for exeuction | Qty. | Unit | Rate | Amount |
|---------|---|--------|------|-----------------------------|------------------|
| 1 | Fixing Marble in floors or steps & landing on 25mm. thick bed of CM (1:1) jointed with neat cement slurry including rubbing & polishing including cost of marble. | 49.44 | Sqm | 1598.70 | 79039.73 |
| 2 | Fixing Wall Tile to dados skirting & risers of steps on 12mm. thick C.P (1:3) jointed with neat cement slurry mixed with pigments to match the shade of wall | 27.27 | Sqm | 978.00 | 26670.06 |
| 3 | Distemper two coat with approved quality and shade over one coat of wall primer of approved | 120.56 | Sqm | 174.00 | 20977.44 |
| 4 | weather coat two coats with approved quality and shade over one coat of wall primer of approved shade on new work to give an even shade including cost & conveyancy of all material etc | 94.76 | Sqm | 184.50 | 17483.22 |
| 5 | Providing enamel painting two coat over a coat of primer including cost & conveyance of all materials etc. | 60.00 | Sqm | 265.80 | 15948.00 |
| 6 | Provision for Transparency Board | 1.00 | Item | 9000.00 | 9000.00 |
| | | | | Total Estimated cost | 169118.45 |
| | | | | Say | 169118.00 |

Rupees One Lakh Sixty Nine Thousand One Hundred Eighteen Only

Asst. Engineer,
NAC,Athagarh

Municipal Engineer,
NAC, Athagarh

Executive Officer,
NAC, Athagarh

To be filled in by the Contractor participating in the tender process

My quoted reate are

_____ % (_____) Excess

OR

_____ % (_____) Less

Over the estimated cost as put to tender

Signature of Contractor

