

Schedule of Quantity for the work "Construction of RCC Slab covering the drain from Sanatan Sahoo res.to Hari Sahoo res. In w. no.13 "

Sl. No.	Description of the work proposed for exeuction	Qty.	Unit	Rate	Amount
1	Dismantling & removing the old cement concrete including stacking the useful materials for reuse & removing the debris within initial lead & lift.	3.60	Cum	858.60	3090.96
2	Providing RCC M-20 by using 10mm to 20mm size hard granite chips (cb) including cost, conveyance & royalty of all materials etc.	6.75	Cum	6024.30	40664.03
3	Straightning, cutting , bending & binding the MS rod & placing in proper position including cost, conveyance of MS rod & binding wire 18 gauge etc.	4.25	Qtl	8671.60	36854.30
4	Providing & laying CC(1:2:4) in road work using 12mm size screened,washed hard black crusher broken granite of approved quality including cost, conveyance, royalty and taxes of all materials , cost of all labour,T&P etc. as per the direction of ELC.	3.24	Cum	7580.60	24561.14
5	Providing rigid & smooth centering & shuttering for concrete work.	80.70	Sqm	248.70	20070.09
6	Removing the slab & fixing over the drain by engagement of labour.	125.00	Each	112.28	14035.00
7	Removal of excavated / dismantled materials by machanical means to an average lead of 5km.	3.60	Cum	278.77	1003.57
				Total Estimated cost	140279.09
				Say	140279.00

Rupees One Lakh Fourty Thousand Two Hundred Seventy Nine Only

Asst. Engineer,
NAC,Athagarh

Municipal Engineer,
NAC, Athagarh

Executive Officer,
NAC, Athagarh

To be filled in by the Contractor participating in the tender process

My quoted reate are

_____ % (_____) Excess

OR

_____ % (_____) Less

Over the estimated cost as put to tender

Signature of Contractor

