

Schedule of Quantity for the work"Construction of Cement Concrete road Near Satyabhama Tripathi house in w. no.15.. ,NAC,Athagarh."

Sl. No.	Description of the work proposed for exeuction	Qnty.	Unit	Rate	Amount
1	Earth work in excavation in all kinds of soil including dressing & levelling the bed & depositing soil within initial lead & lift.	2.16	Cum	300.83	649.79
2	Supplying and filling the foundation and plinth with clean coarse river sand of approved quality from approved quarry, laying in layers not exceeding 150mm thick, watering and ramming including cost, conveyance royalty and taxes of all materials, cost of as per the direction of Engineer-In-Charge.	9.72	Cum	1475.70	14343.80
3	Providing cement concrete(1:3:6) by using 40mm size hard granite metal(cb) includng cost, conveyance & roylaty of all materials etc.	9.72	Cum	5941.00	57746.52
4	Providing & laying cement concrete (1:2:4) by using12mm size hard granite chips(cb) includng cost, conveyance & royalty of all materials	11.88	Cum	7580.60	90057.53
5	Providing rigid & smooth centering & shuttering for concrete work.	10.80	Sqm	249.80	2697.84
6	Removal of Excavated earth by machanical means to an average lead of 5km.	2.16	Cum	278.77	602.14
				Total Estimated cost	166097.63
				Say	166098.00

Rupees One Lakh Sixty six Thousand Ninty Eight Only

Asst. Engineer,
NAC,Athagarh

Municipal Engineer,
NAC, Athagarh

Executive Officer,
NAC, Athagarh

To be filled in by the Contractor participating in the tender process

My quoted reate are

_____ % (_____) Excess

OR

_____ % (_____) Less

Over the estimated cost as put to tender

Signature of Contractor

