

Schedule of Quantity for the work "Construction of RCC Slab covering the drain from Bidyadhar Pradhan res. To Pramod Sahu res. in w. no.16 "

| Sl. No. | Description of the work proposed for exeuction | Qty. | Unit | Rate | Amount |
|---------|---|--------|------|-----------------------------|------------------|
| 1 | Dismantling & removing the old cement concrete including stacking the useful materials for reuse & removing the debris within initial lead & lift. | 0.60 | Cum | 858.60 | 515.16 |
| 2 | Providing RCC M-20 by using 10mm to 20mm size hard granite chips (cb) including cost, conveyance & royalty of all materials etc. | 9.12 | Cum | 6024.30 | 54941.62 |
| 3 | Straightning, cutting , bending & binding the MS rod & placing in proper position including cost, conveyance of MS rod & binding wire 18 gauge etc. | 5.75 | Qtl | 8671.60 | 49823.54 |
| 4 | Providing & laying CC(1:2:4) in road work using 12mm size screened,washed hard black crusher broken granite of approved quality including cost, conveyance, royalty and taxes of all materials , cost of all labour,T&P etc. as per the direction of ELC. | 1.35 | Cum | 7580.60 | 10233.81 |
| 5 | Providing rigid & smooth centering & shuttering for concrete work. | 71.20 | Sqm | 248.70 | 17707.44 |
| 6 | Removing the slab & fixing over the drain by engagement of labour. | 190.00 | Each | 112.28 | 21333.20 |
| 7 | Removal of excavated / dismantled materials by machanical means to an average lead of 5km. | 0.60 | Cum | 278.77 | 167.26 |
| | | | | Total Estimated cost | 154722.03 |
| | | | | Say | 154722.00 |

Rupees One Lakh Fifty Four Thousand Seven Hundred Twenty Two Only

Asst. Engineer,
NAC,Athagarh

Municipal Engineer,
NAC, Athagarh

Executive Officer,
NAC, Athagarh

To be filled in by the Contractor participating in the tender process

My quoted reate are

_____ % (_____) Excess

OR

_____ % (_____) Less

Over the estimated cost as put to tender

Signature of Contractor

