

Schedule of Quantity for the work"Construction of RCC Slab for covering the drain from Siba Swain to Jagannath Matha in w no.2 "

| Sl. No. | Description of the work proposed for exeuction | Qnty. | Unit | Rate | Amount |
|---------|---|-------|------|-----------------------------|-----------------|
| 1 | Providing RCC M-20 by using 10mm to 20mm size hard granite chips (cb) including cost, conveyance & royalty of all materials etc. | 2.70 | Cum | 6024.30 | 16265.61 |
| 2 | Straightning, cutting , bending & binding the MS rod & placing in proper position includng cost, conveyance of MS rod & binding wire 18 gauge etc. | 1.70 | Qtl | 8671.60 | 14741.72 |
| 3 | Providing & laying CC(1:2:4) in road work using 12mm size screened,washed hard black crusher broken granite of approved quality including cost, conveyance, royalty and taxes of all materials , cost of all labour,T&P etc. as per the direction of EIC. | 0.45 | Cum | 7580.60 | 3411.27 |
| 4 | Providing rigid & smooth centering & shuttering for concrete work. | 21.00 | Sqm | 248.70 | 5222.70 |
| 5 | Removing the slab & fixing over the drain by engagement of labour. | 50.00 | Each | 112.28 | 5614.00 |
| | | | | Total Estimated cost | 45255.30 |
| | | | | Say | 45255.00 |

Rupees Fourty Five Thousand Two Hundred Fifty Five Only

Asst. Engineer,
NAC,Athagarh

Municipal Engineer,
NAC, Athagarh

Executive Officer,
NAC, Athagarh

To be filled in by the Contractor participating in the tender process

My quoted reate are

_____ % () Excess

OR

_____ % () Less

Over the estimated cost as put to tender

Signature of Contractor

