

Schedule of Quantity for the work" Repair & Reconstruction of road Near Subhransu Sekhar Das house at Rajbati Nagar in Ward no-18 , NAC Athgarh "

Sl. No.	Description of the work proposed for exeuction	Qty.	Unit	Rate	Amount
1	Supplying and filling the foundation and plinth with clean coarse river sand of approved quality from approved quarry, laying in layers not exceeding 150mm thick, watering and ramming including cost, conveyance royalty and taxes of all materials, cost of as per the direction of Engineer-In-Charge	1.32	Cum	1475.70	1947.92
2	Providing cement concrete(1:3:6) by using 40mm size hard granite metal(cb) includng cost, conveyance & roylaty of all materials etc.	1.32	Cum	5919.90	7814.27
3	Providing cement concrete (1:2:4) by using 12mm size hard granite metal (cb) includng cost, conveyance & royalty of all materials etc.	15.51	Cum	7580.60	117575.11
4	Providing Rigid & smooth centering & shuttering for concrete work	40.80	Sqm	248.70	10146.96
				Total Estimated cost	137484.26
				Say	137484.00

Rupees One Lakh Thirty seven Thousand Four Hundred Eighty Four Only

Asst. Engineer,
NAC,Athagarh

Municipal Engineer,
NAC, Athagarh

Executive Officer,
NAC, Athagarh

To be filled in by the Contractor participating in the tender process

My quoted reate are

_____ % (_____) Excess

OR

_____ % (_____) Less

Over the estimated cost as put to tender

Signature of Contractor