

**Schedule of Quantity for the work" Construction of road from Samal Babu house to Jugol Kishor Bhuyan house in ward no-18, NAC, Athagarh"**

Sl. No.	Description of the work proposed for exeuction	Qty.	Unit	Rate	Amount
1	Earth work in excavation in all kinds of soil including dressing & levelling the bed & depositing soil within initial lead & lift.	28.24	Cum	300.83	8495.44
2	Supplying and filling the foundation and plinth with clean coarse river sand of approved quality from approved quarry, laying in layers not exceeding 150mm thick, watering and ramming including cost, conveyance royalty and taxes of all materials, cost of as per the direction of Engineer-In-Charge	23.56	Cum	1475.70	34767.49
3	Providing cement concrete(1:3:6) by using 40mm size hard granite metal(cb) including cost, conveyance & roylaty of all materials etc.	23.56	Cum	5941.00	139969.96
4	Providing cement concrete (1:2:4) by using 12mm size hard granite metal (cb) including cost, conveyance & royalty of all materials etc.	28.24	Cum	7580.60	214076.14
5	Providing Rigid & smooth centering & shuttering for concrete work	31.20	Sqm	249.80	7793.76
6	Removal of excavataed and dismantled materials by machanical means to an average lead of 5km.	28.24	Cum	278.77	7872.46
7	Add for Transparency Board	1.00	Item	9000.00	9000.00
				<b>Total Estimated cost</b>	<b>421975.25</b>
				<b>Say</b>	<b>421975.00</b>

**Rupees Four Lakh Twenty One Thousand Nine Hundred Seventy Fiive Only**

**Asst. Engineer,**  
NAC,Athagarh

**Municipal Engineer,**  
NAC, Athagarh

**Executive Officer,**  
NAC, Athagarh

**To be filled in by the Contractor participating in the tender process**

**My quoted reate are**

\_\_\_\_\_ % ( ) Excess

**OR**

\_\_\_\_\_ % ( ) Less

**Over the estimated cost as put to tender**

**Signature of Contractor**