

Schedule of Quantity for the work"Repair & Renovation of Padmasahi Kothaghara in w. no.2,NAC, Athagarh."

Sl. No.	Description of the work proposed for exeuction	Qnty.	Unit	Rate	Amount
1	Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32 mm x 32 mm x 2 mm in 3 rows in stair case as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T&P etc. required for the complete in all respect.C/C and stainless square pipe bracing of size case as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T&P etc. required for the complete in all respect.	44.00	Mtr	3624.80	159491.20
2	Supplying, fitting & fixing MS grill Door including cost & conveyance of all materials etc.	95.00	kg	90.00	8550.00
3	Providing 16mm thick cement Plaster (1:6) over brick masonry including cost , conveyance & royalty of all materials etc.	9.60	Sqm	288.10	2765.76
4	weather coat two coats with approved quality and shade over one coat of wall primer of approved shade on new work to give an even shade including cost & conveyancy of all material etc	61.13	Sqm	184.50	11278.49
5	Supplying, fitting and fixing vetrified tile in floors of size 600mm x 600mm of approved make confirming to IS 13755 laid on 20 mm thick cement mortar 1:4 and filling joints with white cement of approved quality including cost of all materials, labour T&P etc required for the work all complete as per direction of Engineer in charge (For new work only)	16.21	Sqm	1149.80	18632.51
6	Distemper two coat with approved quality and shade over one coat of wall primer of approved	102.12	Sqm	174.00	17768.88
7	Providing enamel painting two coat over a coat of primer including cost & conveyance of all materials etc.	15.44	Sqm	265.80	4102.62
8	Supplying fitting, fixing fully glazed aluminum framed openable windows using 15 micron anodized aluminum section 2082 as out section, 9139 as mullion section, 4124 as a shutter section frame with tapered clip of section 4125, aluminum angle , rubber beading, friction stay and handle etc.including cost of glass.	4.80	Sqm	4600.00	22082.88
9	Provision for Transparency Board	1.00	Item	9000.00	9000.00
				Total Estimated cost	253672.34
				Say	253672.00

Rupees Two Lakh Fifty Three Thousand Six Hundred Seventy Two Only

Asst. Engineer,
NAC,Athagarh

Municipal Engineer,
NAC, Athagarh

Executive Officer,
NAC, Athagarh

To be filled in by the Contractor participating in the tender process

My quoted reate are

_____ % (_____) Excess

OR

_____ % (_____) Less

Over the estimated cost as put to tender

Signature of Contractor

