

**Schedule of Quantity for the work "Pot hole repair of different roads in w. no.10,11,12,13 &17, NAC, Athagarh "**

Sl. No.	Description of the work proposed for exeuction	Qty.	Unit	Rate	Amount
1	Dismantling & removing the old cement concrete including stacking the useful materials for reuse & removing the debris within initial lead & lift.	10.71	Cum	858.60	9195.61
2	Providing cement concrete (1:3:6) by using 40mm size hard granite metal (cb) including cost, conveyance & royalty of all materials etc.	1.62	Cum	5941.00	9624.42
3	Providing & laying CC(1:2:4) in road work using 12mm size screened,washed hard black crusher broken granite of approved quality including cost, conveyance, royalty and taxes of all materials , cost of all labour,T&P etc. as per the direction of EIC.	10.71	Cum	7580.80	81190.37
				<b>Total Estimated</b>	<b>100010.39</b>
				<b>Say</b>	<b>100010.00</b>

**Rupees One Lakh Ten Only**

**Asst. Engineer,**  
NAC,Athagarh

**Municipal Engineer,**  
NAC, Athagarh

**Executive Officer,**  
NAC, Athagarh

**To be filled in by the Contractor participating in the tender process**

**My quoted reate are**

\_\_\_\_\_ % ( ) Excess

**OR**

\_\_\_\_\_ % ( ) Less

**Over the estimated cost as put to tender**

**Signature of Contractor**

