

Schedule of Quantity for the work "Pot hole repair of different roads in w. no.8,9,15,16 &18, NAC, Athagarh "

Sl. No.	Description of the work proposed for exeuction	Qnty.	Unit	Rate	Amount
1	Dismantling & removing the old cement concrete including stacking the useful materials for reuse & removing the debris within initial lead & lift.	14.31	Cum	858.60	12286.57
2	Providing cement concrete (1:3:6) by using 40mm size hard granite metal (cb) includng cost, conveyance & royalty of all materials etc.	1.62	Cum	5941.00	9624.42
3	Providing & laying CC(1:2:4) in road work using 12mm size screened,washed hard black crusher broken granite of approved quality including cost, conveyance, royalty and taxes of all materials , cost of all labour,T&P etc. as per the direction of EIC.	14.31	Cum	7580.80	108481.25
				Total Estimated cost	130392.23
				Say	130392.00

Rupees One Lakh Thirty Thousand Three Hunderd Ninety Two Only

Asst. Engineer,
NAC,Athagarh

Municipal Engineer,
NAC, Athagarh

Executive Officer,
NAC, Athagarh

To be filled in by the Contractor participating in the tender process

My quoted reate are

_____ % (_____) Excess

OR

_____ % (_____) Less

Over the estimated cost as put to tender

Signature of Contractor

