

Schedule of Quantity for the work" Repair & renovation of Keutasahi Kothaghara in W.no.-4 , NAC,Athagarh."

Sl. No.	Description of the work proposed for exeuction	Qnty.	Unit	Rate	Amount
1	DISmantling & removing 2.5 Ccm thick artificial stone flooring including stacking the useful materials for reuse & removing the debris within 50m lead	35.88	Sqm	115.90	4158.49
2	Dismantling and removing 2.5 cm thick grading concrete including staking the useful materila for reuse & removing the debris within initial lead & lift.	56.43	Sqm	130.40	7358.47
3	Fixing Tiles in floors or steps & landing on 25mm. thick bed of cement mortar (1:1) jointed with neat cement slurry mixed with pigment to match the shades of the tiles all complete with & without cost of precast tiles.	36.72	Sqm	1025.90	37671.05
4	Fixing Wall Tile to dados skirting & risers of steps on 12mm. thick C.P (1:3) jointed with neat cement slurry mixed with pigments to match the shade of wall	46.76	Sqm	1425.40	66651.70
5	Supplying, fitting & fixing MS Door , window & Collapsible Gate including cost & conveyance of all materials etc.	327.00	kg	90.00	29430.00
6	4cm. thick grading CC (1:2:4) on roof slab with 12mm. Size hard broken & down grade Size on old work	56.43	Sqm	834.00	47062.62
7	6 mm thick cement plaster (1:4) to R CC surfaces finished smooth including closed deep chiping and slurry treatment	44.36	Sqm	218.60	9697.97
8	Providing enamel painting two coat over a coat of primer including cost & conveyance of all materials etc.	19.05	Sqm	265.80	5063.49
9	Distemper two coat with approved quality and shade over one coat of wall primer of approved	103.83	Sqm	174.00	18065.55
10	weather coat two coats with approved quality and shade over one coat of wall primer of approved shade on new work to give an even shade including cost & conveyancy of all material etc	108.33	Sqm	184.50	19987.62
11	Provision for Transparency Board	1.00	Item	9000.00	9000.00
				Total Estimated cost	254146.96
				Say	254147.00

Rupees Two Lakh Fifty four Thousand One Hundred fourty Seven Only

Asst. Engineer,
NAC,Athagarh

Municipal Engineer,
NAC, Athagarh

Executive Officer,
NAC, Athagarh

To be filled in by the Contractor participating in the tender process

My quoted reate are

_____ % (_____) Excess

OR

_____ % (_____) Less

Over the estimated cost as put to tender

Signature of Contractor