

**Schedule of Quantity for the work"Construction of RCC Slab for Covering the drain near Trinath temple in w. no.7 "**

Sl. No.	Description of the work proposed for exeuction	Qty.	Unit	Rate	Amount
1	Dismantling & removing the old cement concrete including stacking the useful materials for reuse & removing the debris within initial lead & lift.	0.68	Cum	858.60	579.56
2	Providing RCC M-20 by using 10mm to 20mm size hard granite chips (cb) including cost, conveyance & royalty of all materials etc.	6.12	Cum	6024.30	36868.72
3	Straightning, cutting , bending & binding the MS rod & placing in proper position includng cost, conveyance of MS rod & binding wire 18 gauge etc.	3.86	Qtl	8671.60	33434.22
4	Providing & laying CC(1:2:4)) in road work using 12mm size screened,washed hard black crusher broken granite of approved quality including cost, conveyance, royalty and taxes of all materials , cost of all labour,T&P etc. as per the direction of FIC.	0.34	Cum	7580.60	2558.45
5	Providing rigid & smooth centering & shuttering for concrete work.	47.70	Sqm	248.70	11862.99
6	Removing the slab & fixing over the drain by engagement of labour.	120.00	Each	112.28	13473.60
7	Removal of excavated / dismantled materials by machanical means to an average lead of 5km.	0.68	Cum	278.77	188.17
				<b>Total Estimated cost</b>	<b>98965.70</b>
				<b>Say</b>	<b>98966.00</b>

**Rupees Ninty Eight Thousand Nine Hundred Sixty Six Only**

**Asst. Engineer,**  
NAC,Athagarh

**Municipal Engineer,**  
NAC, Athagarh

**Executive Officer,**  
NAC, Athagarh

**To be filled in by the Contractor participating in the tender process**

**My quoted reate are**

\_\_\_\_\_ % ( \_\_\_\_\_ ) Excess

**OR**

\_\_\_\_\_ % ( \_\_\_\_\_ ) Less

**Over the estimated cost as put to tender**

**Signature of Contractor**

